Form Approved REPORT DOCUMENTATION PAGE OMB No. 0704-0188 Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing this collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0704-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. PLEASE DO NOT RETURN YOUR FORM TO THE ABOVE ADDRESS. 3. DATES COVERED (From - To) 1. REPORT DATE (DD-MM-YYYY) 2. REPORT TYPE 28-10-2011 **Briefing Charts** 4. TITLE AND SUBTITLE 5a. CONTRACT NUMBER **5b. GRANT NUMBER** Project Themis: PIV Measurement of Elbow Flow through a Flow Conditioner 5c. PROGRAM ELEMENT NUMBER 6. AUTHOR(S) 5d. PROJECT NUMBER Benjamin Miller 5f. WORK UNIT NUMBER 33SP0795 7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) 8. PERFORMING ORGANIZATION REPORT NUMBER Air Force Research Laboratory (AFMC) AFRL/RZSE 4 Draco Drive Edwards Air Force Base CA 93524-7160 9. SPONSORING / MONITORING AGENCY NAME(S) AND ADDRESS(ES) 10. SPONSOR/MONITOR'S ACRONYM(S) Air Force Research Laboratory (AFMC) 11. SPONSOR/MONITOR'S AFRL/RZS NUMBER(S) 5 Pollux Drive Edwards AFB CA 93524-7048 AFRL-RZ-ED-VG-2011-438 12. DISTRIBUTION / AVAILABILITY STATEMENT Distribution A: Approved for public release; distribution unlimited (PA#11932). 13. SUPPLEMENTARY NOTES Thesis Presentation, University of California at Los Angeles, December 2011. 14. ABSTRACT This presentation provides data for validation of a CFD study done on a VORTAB flow conditioner. Objectives include achievement of a full-developed turbulent velocity profile for pipe flow. Secondary flow will cause a flow meter to register unexpected results. VORTAB reduces straight run distance with a minimal pressure loss and minimal validation of the component. CFD simulations, using LH2, showed that the pipe with a VORTAB generated more vorticity at the exit than the pipe without a VORTAB. 15. SUBJECT TERMS

17. LIMITATION

OF ABSTRACT

SAR

18. NUMBER

23

OF PAGES

16. SECURITY CLASSIFICATION OF:

b. ABSTRACT

Unclassified

c. THIS PAGE

Unclassified

a. REPORT

Unclassified

19a, NAME OF RESPONSIBLE

19b. TELEPHONE NUMBER

Mr. Nils M. Sedano

(include area code)

PERSON

N/A



Project Themis: PIV Measurement of Elbow Flow through a Flow Conditioner



Benjamin Miller AFRL/RZSE (Jackson and Tull) Air Force Research Laboratory

PA#11932



Profile



• B.S., Mechanical Engineering, May 2010, Virginia Tech



M.S., Aerospace Engineering, UCLA



- Past Research Experience
 - NASA Ames Research Center
 - Army Research Laboratory
 - Virginia Tech Senior Design Project
- Future Work
 - Intern with SpaceX
 - Finish Masters Degree






Background



Research Objective:

Provide data for validation of a CFD study done on a VORTAB flow conditioner



www.fluidcomponents.com


- Achieve a fully-developed turbulent velocity profile for pipe flow
- Secondary flow will cause a flow meter to register unexpected results
- VORTAB reduces straight run distance with a minimal pressure loss
- Minimal validation of component
- CFD simulations, using LH2, showed that the pipe with a Vortab generated more vorticity at the exit than the pipe without a Vortab.

PA#11932




Particle Image Velocimetry (PIV)





www.LaVision.com

- PIV is an optical technique used to obtain instantaneous velocity measurements
- The main flow is seeded with particles
- Particles are illuminated using a laser and tracked to produce a vector field






Particle Image Velocimetry (PIV)


PA#11932




 Frame-Straddling is a technique in which the lasers pulses on sequential frames



 A velocity is computed using the time between laser shots





Frame 2

Pulse 2


Frame 1



Test Facility



VORTAB placed one diameter downstream of elbow






Experimental Setup




Laskin Nozzle



- Inner Diameter = 2"
- Mean Velocity = 9.63 m/s
- Reynolds Number = 32,000

PVC Pipe L/D = 30

Phantom V210 Camera VORTAB Flow Conditioner




90°Long Curve Elbow

PA#11932




Experimental Setup





Acrylic Test Section








PA#11932



Initial Test Conditions






r/D

-0.5

A fully developed pipe flow was found in the test section upstream of the elbow



0.5



CFD Cases for Comparison



Reynolds number	Fluid	Vortab location	Comment
			USET
9,000,000	LH2	9D	installation
32,000	Air	9D	For Validation


Additional details

- Fluent
- k-ε turbulence model
- Differences in geometry between the experimental and computational work:
 - Vortab location
 - Downstream contraction
 - □ Bend curvature
 - Vortab clocking



Nearfield Mean Vorticity Downstream of Elbow









Nearfield Mean Vorticity Downstream of Elbow










Nearfield Mean Vorticity Downstream of Elbow








VORTAB Comparisons



Experiment for VORTAB at 1D downstream of elbow



CFD for VORTAB at 9D downstream of elbow (USET installation) and with contraction





The experiment was unable to resolve the vorticity entering the vortab for the 9D installation location, therefore focus was placed on the effects of the vortab located closer to the elbow (i.e. 1D location).




Nearfield Mean Vorticity Downstream of VORTAB










PA#11932



Mean Vorticity Downstream of VORTAB








Vortex Dynamics at High Reynolds Number



Re = 9,000,000





Conclusions



- Fully-developed turbulent pipe flow as initial condition
- Counter-rotating vortices were found at varying distances downstream of the elbow
- Experiment and CFD agree very well with and without the VORTAB installed

- VORTAB disrupts secondary flow for both configurations (experiment and CFD) at moderate Reynolds number
- New vortex dynamics emerge at high Reynolds number based on CFD simulations—unable to validate experimentally






Questions?



Recommendations



- Perform a CFD examination of experiment
- Test other flow conditioners
- Trouble resolving vorticity
 - Stereoscopic PIV





www.piv.de



Correlation Map









Terminal Velocity



$$d = 1 micron$$

$$V_t = \sqrt{\frac{2mg}{\rho A C_d}} = 5.27 \frac{mm}{s}$$

$$d_t = 15 * 10^{-6} sec$$

$$V_t * d_t = 7.91 * 10^{-5} mm$$

$$(7.91*10^{-5})*13.2 \frac{pix}{mm} = 0.00104 pix$$

